

PLANNING + DEVELOPMENT

Director
Deputy Director
Chief Planner
Project Management Team
P+UD Staff

Emily Liu, FAICP Andrea Gilles, AICP Patrick Blaydes Lindsay Jackson, Sandra Bowie Sef Okoth, Don Raines, Ted Helm, Asma Shaikh

Taskforce

Scottie Smith, Chairperson Tabitha Wheeler, Co-chairperson, Chris Aslam, Rev. Todd Atkins, SDFP Faith Coalition, Jason Brown, Neighborhood Association, Karim Bryant, APAA, Randall Bryant, Black CHamber, Melanie Ferguson, Matthews Southwest, Quincy Guinyard, Dorothy Hopkins, FRI, Trae Jacob, Colonial Hills NA, Eva Jones, Queen City NA, Hank Lawson, Resident, Traswell Livingston, Brian Luallen, Fair Park First, Linda McMahon, The Real Estate Council, Sherri Mixon, TR Hoover, Celeste Paylor, Diane Ragsdale, ICDC, Clifton Reese, Bonton Farms, Roderick Rollins, Julie Saqueton, St. Phillips, Marco Villegas, Marinan Williams, Southfair CDC

LETTER FROM THE TASK FORCE CHAIR

IN PROGRESS



CONTENTS

PLAN OVERVIEW

- 1 PLANNING PROCESS
- 2 GUIDING PRINCIPLES
- **3 FOCUS AREAS**
- 4 IMPLEMENTATION TABLE

THE FOUR-YEAR PLANNING PROCESS INCLUDED EXTENSIVE COMMUNITY ENGAGEMENT, CONVERSATIONS, AND STRATEGY DEVELOPMENT TO REAFFIRM ESTABLISHED GOALS, CONFIRM UPDATED PRIORITIES, AND IDENTIFY THE ACTIONS AND PARTNERSHIPS NEEDED TO IMPLEMENT THE PLAN.


INTRODUCTION

South Dallas/Fair Park (SDFP) is generally comprised of the area geographically defined by Planned Development District No. 595 (PD595), the South Dallas/Fair Park Special Purpose District. This district spans over 3,000 acres and is bounded by key roads and railways, including Union Pacific Railroad, CF Hawn Freeway, and R.L. Thornton Freeway. The South Second Ave and Elsie Faye Heggins Street intersection is at the center of the area, which also includes the Fair Park, MLK, Hatcher, and Lawnview DART stations. This Area Plan also includes areas immediately adjacent to PD595, including William Blair Jr. Park to the south.

SDFP has a rich history and culture born from the legends of the past and present. The community's power remains within the resilience and fortitude of its residents, community organizations, and local businesses. Although challenged by disinvestment for decades, community groups and advocates never lost faith in the strength and opportunity in this community.

As a renaissance began to occur in South Dallas, a renewed need emerged to reaffirm and update community goals and priorities through a strategic process and coordinated action by a coalition of area groups. This coalition, representing residents, businesses, nonprofit leaders, developers, activists and faith-based organizations, was selected by the District 7 City Council office to represent diverse viewpoints, needs, and solutions for the area.

Given the large number of previous planning efforts within SDFP, the task force championed that this plan should focus on implementation and action, rather than another visioning exercise. Discussions were challenging and passionate, but the task force dug in and stayed in. As a result, this SDFP Area Plan lays an achievable path that promotes change and preservation where desired.



PLAN OVERVIEW

Building on previous initiatives, this plan examines existing conditions, outlines a future land use and urban design vision, and offers recommendations for implementation. The contents of this plan represent multiple years of work by the SDFP task force and community members to reaffirm visions from many past planning efforts and provide an updated lens toward the future of this area. The focus is on action and implementation with an eye toward facilitating vibrant and culturally-grounded development, particularly along walkable retail corridors, while aslo preserving and strengthening the area's unique, historic, and culturally significant neighborhoods.

The Area Plan is organized into four sections as outlined below. The planning process included lively conversation and debate to arrive at the guiding principles and narrowing down the focus areas within the very large planning area. The implementation section is guided by the priorities established in the previous sections. The plan serves as a realistic and actionable guide for achieving the community's vision and facilitating future development.

GUIDING PRINCIPLES

Guiding principles are crucial for maintaining focus and achieving long-term, sustainable success in implementation

(A) LAND USE + ZONING

Amend land use policy and zoning regulations to support the repurposing of vacant and underutilized land uses consistent with the area plan vision.

(C) ECONOMIC DEVELOPMENT

Promote economic growth and sustainable development to pursue catalytic opportunities for commercial and residential development.

(E) COMMUNITY WELL-BEING

Implement land use policies, tools, and incentivies that support improved health, safety, and quality of life for

(B) HISTORY + CULTURE

Protect, support and celebrate South Dallas Fair Park history, culture, people and architecture.

INFRASTRUCTURE

Advance safe, compact, walkable, mixed use development around DART stations and other transportation nodes to increase connectivity and access to housing and job opportunities.

F HOUSING + DESIGN

Preserve existing housing stock for current homeowners and renters, ease displacement pressure on existing residents and align opportunities for creating diverse housing options.

PLANNING PROCESS

Planning process involved engaging stakeholders, setting goals, defining objectives, identifying actions, and establishing timelines for implementation.

FOCUS AREAS

Focus areas are chosen based on community input, stakeholder priorities, and alignment with the plan's goals.

Extensive community outreach during the four-year planning process revealed that current needs differ from two decades ago when PD 595 was established. The updated plan reflects ongoing changes, including new development, residential growth, and infrastructure improvements in neighborhoods like Mill City, Queen City, and Bonton. It provides a foundation for zoning



2ND AVENUE

- **ELSIE FAYE HEGGINS STREET**
- MALCOLM X BLVD CORRIDOR
- MARTIN LUTHER KING JR. DART STATION
- QUEEN CITY NEIGHBORHOOD

DEMOGRAPHICS + LANDUSE & ZONING

Demographic and land use data are essential for understanding community needs, planning infrastructure, and guiding development.

Population: 31,543

and economic viability.

Major Race: African American

Housing Units: 12,418

Major Land-Uses: Residential and Commercial Major Zoning Category: PD & Industrial Zoning

LEGACY BUILDERS & NEW PROJECTS

These efforts drive development, create jobs, attract investment, and align with community goals, making them pivotal in advancing the planning process. Some of those projects are:

- Park South Family YMCA
- Forest Theater Redevelopment
- Cornerstone Baptist Church Master Plan
- St. Philip's School and Community Center
- Bonton Farms
- Frazier Revitalization

4 IMPLEMENTATION

Including objectives and action items in a plan is crucial as they provide clarity and a structured roadmap for achieving the plan's vision.

OBJECTIVES

Defines specific, measurable targets to achieve the plan's goals.



ACTION ITEMS Outlines tasks and

steps needed to accomplish objectives.

Plan recommendations are summarized in the implementation tables organized by actions, timelines, responsibilites and resources to ensure accountability and progress tracking.

Key and lead partners are needed to provide leadership, expertise, and resources for successful plan execution.

LEAD

Coordinates efforts and ensures progress on the plan's implementation.



Collaborates to provide resources, expertise, or support.

KEY PARTNERS

BACKGROUND

effort began with a five-signature memo submitted by Councilmember Adam Bazaldua (District 7) and co-signed by Councilmembers Jaime Resendez (District 5), Paula Blackmon (District 9), Omar Narvaez (District 6), and Adam Medrano (District 2). Shortly after authorization, the request was halted due to the onset of the COVID-19 pandemic. During this time of pause, it became evident that an area plan was necessary to support the authorized hearing (zoning) process.

Area plans, which are also City-initiated and City Council-adopted, aim to create a future growth vision for multiple neighborhoods while addressing infrastructure improvements and other land-use concerns. Councilmember Bazaldua formed the South Dallas/Fair Park Area Plan Taskforce to guide the process and ensure diverse perspectives and input. The taskforce, consisting of 23 members, included community leaders from multidisciplinary institutions, neighborhood association presidents, and representatives from organizations such as the Landmark Commission, Dallas Black Chamber, Bonton Farms, and Fair Park First.

The early taskforce meetings were challenging, with stakeholders somewhat in silos, advocating for the unique meet during a pandemic. There was also struggle to resolve
This plan proposes to tackle those issues. visioning for an area that had been planned over and over

In January 2020, this planning and community engagement for decades, without much result. Over time, a shift in leadership and focus on the task force led to an agreement that an implementation-driven approach, rather than solely a land-use vision, would better serve the community.

> Those many past planning efforts, including the 2001 South Dallas/Fair Park Economic Development Corridor Plan, which catalyzed PD 595, were reviewed by City staff and the taskforce, and established the blueprint for this plan. Many of the past plans addressed immediate needs, such as a pathway toward eliminating nuisance properties, however, the longer-term vision of active and culturally celebrated businesses and institutions and quality housing for South Dallas residents fell short. As a result, the area was left with an abundance of vacant buildings and restrictive development codes, now seen as barriers to growth.

The SDFP community is advocating for change, demanding answers about proposed infrastructure projects, the increasing numbers of unsheltered individuals, and the lack of locally-based economic development. Longtime residents and influential community leaders emphasize the urgency to protect the area's cultural identity and address displacement pressures. Change is already evident in the area. Along Pennsylvania Avenue, vacant lots are transforming into contemporary homes priced above the city's median needs of their individual neighborhoods and/or organizations average housing price, signaling rapid development and a within this very large planning area, all while managing to need for proactive planning to ensure equitable outcomes.



CONTEXT **ANALYSIS**

Understand the existing conditions, including demographics, land use, infrastructure, and community needs.



COMMUNITY ENGAGEMENT

Gather input through workshops, surveys, and discussions to identify priorities and challenges.



VISION **SETTING**


Develop a shared vision and define goals to guide future development and improvements.



PLAN **IMPLEMENTATION**

Outline action steps, identify key partners. and allocate resources to execute the plan effectively.

STUDY AREA



STRATEGIC APPROACH

The Taskforce adopted a strategic approach to prioritize In summer 2022, planning staff began engaging the

Taskforce identified five priority areas: 2nd Avenue, Elsie Faye Heggins Street, Malcolm X Boulevard, Martin Luther King, Jr. DART Station, and Queen City. South Dallas/Fair Park (SDFP) stakeholders emphasized

Ragsdale, the Taskforce formed two internal working groups. One group focused on Housing and proposed the need for residential design standards. The other group reviewed require Specific Use Permits (SUPs).

key issues for stakeholders and integrate relevant land use broader community, visiting faith-based organizations, elements into the broader ForwardDallas 2.0 Comprehensive businesses, non-profits, neighborhood associations, Land Use Plan. They identified six guiding principles: and other stakeholders in South Dallas. The first public Land Use and Zoning, Housing, Economic Development, meeting was held at the South Dallas Cultural Center Infrastructure, Community Wellbeing, and History and Culture. in December 2022, where residents provided feedback on the guiding principles, focus areas, and additional The next milestone involved determining focus areas community development concerns related to land use within South Dallas. After months of deliberation, the and development. This effort aimed to create a timely, implementation-focused plan achievable within five years.


the need for their voices to be heard. The planning process To address challenges such as "grossly incompatible housing fostered greater coordination in prioritizing needs and types," a term coined by former Councilwoman Ms. Diane determining actionable next steps. Community leaders are demanding answers to pressing issues, including public works, homelessness, and the rapid development that risks displacing long-time residents. The urgency for change Planned Development 595 to recommend new uses, resolve is palpable, as new developments and rising home values barriers in the ordinance, and identify uses that should still transform neighborhoods, bringing both opportunity and challenges.













HISTORICAL CONTEXT


history shaped by racial segregation, economic became a cultural hub for Dallas' Black community, inequality, and resilience. Originally a working-class fostering thriving neighborhoods, white neighborhood, it transitioned to a predominantly Black community during the early-to-mid 20th South Dallas/Fair Park remains a symbol of Black heritage century due to a combination of redlining, restrictive and cultural significance, with efforts now focused on covenants, and the Great Migration of African Americans seeking opportunities in northern and western cities. long-standing disparities.


Fair Park itself played a central role in racial segregation; though it was a site for major events like the Texas Centennial Exposition in 1936, Black residents were excluded or segregated from many facilities. Post-World War II urban renewal projects, highway construction, and disinvestment led to significant displacement and economic decline in the area.


The South Dallas/Fair Park area has a rich but complex Despite these challenges, over time, the area and institutions despite systemic barriers. equitable revitalization to honor its history while addressing

> In the past two decades much work has been accomplished to help revitalize South Dallas. Twenty years ago, the zoning was changed to help remove "bad actor" businesses that plagued South Dallas. Housing and Community groups like ICDC, Frazier Revitalization Habitat, Cornerstone Baptist Church, St. Phillips School, Bonton Farms, Forward Forest Theater and others have built housing, supportive services and a created network of organizations dedicated to South Dallas residents.

DEMOGRAPHICS








EXISTING LAND USE

land use in South Dallas/Fair Park. This is mainly due to Fair Park (Northwest section of the map), Oakland Cemetery (Center on the map), and The flood plain where White Rock Creek meets the Trinity river (eastern portion of the map).

South Dallas/Fair Park is primarily represented by single family attached and detached land uses, as shown in yellow Lastly, there is a high amount of institutional (blue) existing on the map. Many of the historic neighborhoods in South Dallas like Queen City, Mill City, Wheatly Place, Ideal and Bonton are located in these residential land use areas.

Parks and open space represent a large portion of the existing Commercial, represented in red is generally located along major streets. It is important to note that in both the commercial areas and within the residential areas that there is a good amount of vacant land. Industrial land uses represented in various hues of purple, are located along and between the freeways, as well as along Botham Jean Blvd.


> land use. Institutional land uses include schools, community centers, churches and other faith-based organizations, nonprofits and government buildings.



EXISTING ZONING

Much of South Dallas is under Planned Development Permit approved by City Council. It also limits community Number 595 (PD-595/PD). With only slight exceptions, it is a traditional land use based zoning code separating South Dallas into different areas for single family, multifamily or commercial. It is was written roughly twenty-five years ago to address certain issues South Dallas was facing at the time, namely the abundance of convvenience stores that sold beer and wine and little nutritional food. The PD specifically makes those land uses allowable only through a Specific Use

gardens in residential districts because of an abundance of groups outside of South Dallas who established "community gardens" on vacant lots only to abandon them. The PD was also written to act as a master PD meant to dictate the development of South Dallas the way similar PDs act in Oaklawn, the Cedars, or North Oak Cliff.



LEGACY BUILDERS & NEW **PROJECTS**

BACKGROUND

The following organizations have stood firm for more than two decades as pillars of the South Dallas community by building, restoring, and creating opportunites for residents and businesses, despite years of disinvestment in the area. Representatives of each of the organizations continued their commitment to the community by participating in the area planning proess. Their long history has NNERCITY COMMUNITY allowed them to develop a deep understanding of local issues, relationships, and resources, all critical to achieving the vision for South Dallas.

CORNERSTONE COMMUNITY **DEVELOPMENT CORPORATION**

1819 Martin Luther King Jr Blvd. The Cornerstone Community Development Corporation (CCDC) 4 SOUTH FAIR COMMUNITY is dedicated to the acquisition, stabilization, and development of real estate properties within the target area of South Dallas. Their mission is to revitalize the community by providing quality, affordable housing options and fostering economic growth through strategic real estate initiatives. Through our work, we aim to uplift neighborhoods and enhance the 5 ST. PHILIP'S SCHOOL & overall quality of life for residents in South Dallas.

2 FRAZIER REVITALIZATION

4716 Elsie Faye Heggins St. organization prioritizes health access, bridging the

education achievement gap, affordable housing, and community engagement in the historic Frazier neighborhood. Services: Frazier Revitalization provides a range of community-oriented services, including a community lawyering center, after-school programs, and **6 BONTON FARMS** a dental clinic to address residents' needs and promote neighborhood transformation.

DEVELOPMENT CORPORATION

Spring Avenue ICDC's mission is to create a stable, safe, and vibrant, South FOREST THEATER Dallas/Fair Park community by building partnerships that provide homeownership opportunities, economic development, community education, and advocacy. "Building Lives, Revitalizing Neighborhoods".

DEVELOPMENT CORP.

2610 MLK Jr. Blvd.

South Fair's mission is to provide sustainable (affordable) housing for low and moderate-income families through multifamily, single-family, 19 PARK SOUTH FAMILY YMCA economic development, and through the connectivity of social services.

COMMUNITY CENTER

1600 Pennsylvania Ave Vision: To build a vibrant, economically diverse community that honors its rich history while offering residents of all backgrounds opportunities to live, work, play, and thrive. Strategic

Priorities: Collaborative community planning, quality housing, economic development, wellness, and public safety initiatives to improve the quality of life for all South Dallas residents.

6911 Bexar St. Bonton's Bonton's Farm operates a farm-to-table restaurant and provides fresh. locally sourced food to combat food deserts and promote wellness. public safety initiatives to improve the quality of life for all South Dallas residents.


1920 Martin Luther King Jr.

The historic Forest Theater. previously vacant for 15 years is undergoing a major renovation to bring the theater back to life. Included in the proposal is a potential mixed-income housing component for the community development project, which will help diversify the housing in the neighborhood.

2500 Romine Ave

This newly renovated will serve as a critical asset to the Queen City neighborhood and the larger South Dallas/Fair Park area. It features one of the only three saltwater pools in the region, providing opportunities for fitness, recreation, and community programming for residents of all









South Dallas/Fair Park Area Plan - DRAFT - April 2025 South/Dallas Fair Park Area Plan-DRAFT April 2025

CHAPTER OVERVIEW

The task force spent a number of months and numerous meetings thoughtfully discussing what the underlying guiding principles for their work and the area plan. Ultimately they decided on the five listed below. These five principles are meant to be the heart of the work and the recommendations included in the plan.

GUIDING PRINCIPLES


CONTENTS

- A. LAND USE & ZONING
- **B. HISTORY & CULTURE**
- C. ECONOMIC DEVELOPMENT
- D. INFRASTRUCTURE
- E. COMMUNITY WELL BEING
- F. HOUSING + DESIGN

KEY ISSUES 1. Amend PD 595 to address identified land use issues. Develop major commercial corridors to become mixed use corridors and allow residential uses. 3. Develop design standards for single family homes. Amend land use policy and zoning regulations to support 4. Address specific use the repurposing of vacant and underutilized land uses permits and parking. consistent with the area plan vision.

LAND USE + ZONING

GUIDING PRINCIPLES



Develop design guidance for new housing in South Dallas/ Fair Park that is reflective of existing housing in established neighborhoods.

Encourage development of new, diverse housing options at appropriate locations including major corridors and transit hubs.

Much of South Dallas is located within a unique zoning District called, Planned Development 595. It was created twenty years ago to address issues the community was facing at the time. Based on community feedback, new growth in the area, and market changes, an authorized hearing (city-initiated zoning) was initiated for this area. This plan wil guide that future zoning review.

Through much discussion and debate, the task force recommended that as part of the future reiew of the zoning within PD595, that additional design standards be added to the residential areas to promote more compatible development in established neighborhoods. The standards that the task force and the community recommend are detailed in the Housing Design section of the plan.

It was also recommended by the task force that the commercial areas of South Dallas/Fair Park allow for more mixed use to help revitalize those areas and add much needed housing. The full recommendations for changes in the commercial areas are located in the implementation section of the plan, but some of the more prominent changes are included within this section.

To be clear, this area plan does not make these changes. however the recommendations throughout this plan provide guidance for implementation and action to be taken through the zoning, that includes a separate public process.

South/Dallas Fair Park Area Plan-DRAFT April 2025

ACTION STEPS

Amend zoning regulations in the PD that address concerns and issues facing the community today.

- Consider amending the PD to:
 - Allow Catering Services land use by right in the mixed use
 - Allow Restaurant with Food-To-Go land use by right in mixed use subdistrict.
 - Allow Massage uses as an accessory land use to other Personal Service land uses.
 - Include Vape Shops as a Tobacco Store not allowed.
- Review the parking mandate in the PD, and if not addressed through citywide policies, reduce or in some cases remove the parking mandate from the PD.

Prioritize redevelopment of commercial corridors and nodes as mixed use for appropriate scaling and density.

- Review the zoning for the following:
 - o Areas identified as Community Mixed Use for mixed use subdistrict within the PD allowing Low to Mid Rise
 - Areas identified as Neighborhood Mixed Use for mixed use subdistrict within the PD allowing Low Rise buildings.
 - o Areas identified as Regional Mixed Use for mixed use subdistrict within the PD allowing Mid to High Rise buildings.

CONTEXT

Land use describes how people use the land. It refers to the activities people designate to land for various economic or cultural purposes (e.g., agricultural, residential, industrial, and recreational uses).

Where do you go on Saturday mornings for goods and services? This question was presented by Tabitha Wheeler, Co-Chair of the South Dallas/ Fair park taskforce. This question guided the taskforce and South Dallas/Fair Park residents for what specific land uses they wanted to see in their community. Community members expressed the desire for small businesses like coffee shops, smoothie shops, nice restaurants, and many more.

This community feedback ultimately became the basis for the future placetypes for this plan area, as represented in forwardDallas 2.0.

Placetypes describe the long-term vision and desired building and preservation characteristics for different places within the city including neighborhoods, use areas, employment and industry centers, and open spaces. They provide a highlevel guide for the desired mix of land uses, design and the recommended intensity and scale of the different uses.

OVERVIEW



South Dallas developed as an industrial and residential area in the late 19th and early 20th centuries. Its proximity to downtown and major railroads made it a hub for commerce and housing.

By the early 20th century, Jim Crow laws and discriminatory practices relegated African Americans to specific areas, including South Dallas. These policies led to the area's transformation into a predominantly Black community.

South Dallas became a focal point for civil rights activism, with leaders and organizations advocating for desegregation, voting rights, and economic opportunities.

B HISTORY & CULTURE

GUIDING PRINCIPLES

- Protect, support and celebrate South Dallas/Fair Park history, culture, people, and architecture.
- Promote urban design that respects the historic design and architecture of the area.
- B3 Promote and support community spaces that celebrate the community's history.
- Support local small businesses and entrepreneurs, espcially along cultural corridors such as 2nd Avenue, MLK JR, and Malcolm X.

OVERVIEW

South Dallas is rich in culture and historical significance. There are numerous cultural assets throughout South Dallas spanning museums and cultural heritage including artists and musicians, architecture and buildings, neighborhoods, and family friendly spaces and places. The South Dallas community's rich history of prominent community leaders are immortalized by way of major throughfares throughout the community.

As you enter South Dallas from downtown you may find yourself on Al Lipscomb Way, once known as Grand Ave, Al Lipscomb Way is a direct entrance for vehicular traffic to Fair Park. Albert Louis "Al" Lipscomb -seven-term Council member, and advocate for civil rights was born June 15, 1925. He was the lead plaintiff in 1970s lawsuit that successfully challenged Dallas' system of electing every council member citywide, forcing the city to change to a mostly single -member district system.

Elsie Faye Heggins-Council member and civil rights activist, born August 20, 1934, fought for recognition of Dallas's Black heritage through the naming of streets and buildings. It has been said by many Dallas Citizens that "Mrs. Heggins is a true Dallas pioneer, building and fashioning a city that would serve ALL of its citizens, not just a select few for future generations."

ACTION STEPS

Protect South Dallas/Fair Park history and culture.

- Charge the Neighborhood Coalition and SDFP Task Force with establishing a process to select a history and culture committee.
- Pursue historical markers for Mrs. Pearl C Anderson home, and Hayden Grocery Store located in Queen City.
- Celebrate South Dallas/Fair Park history by archiving historical information and creating a living document via on-line publication.
- Work with existing cultural organizations such as South Dallas Cultural Center to collect oral histories from South Dallas residents.
- Collect historical artifacts (photos, videos, memorabilia) of prominent South Dallas families to tell the story of various South Dallas communities.
- Work with local sororities, and fraternities chapters that serve South Dallas and identify historical and cultural events of significance.
- Document and collect history and cultural experiences from FairPark in reference to African Americans. (State Fair Classic, Prairie View A&M & Grambling State)

25

South Dallas/Fair Park Area Plan -DRAFT - April 2025 | South/Dallas Fair Park Area Plan-DRAFT April 2025 |



Cultural Assets are public amenities and elements of communities that create identity and shape external perceptions of place, including cultural facilities & institutions, cultural districts, and neighborhood gateways & identity.

MUHAMMAD ALI A CUSTOMER OF

GRAHAM'S BARBER SHOP



LEFT TO RIGHT: Customer, Jimmie Malone, Marie Cook, Althea Kir brough, Customer, William Schufford, John Coleman - mgr., and two customers.

Cultural Assets

South Dallas is rich with historic and cultural heritage. The following cultural assets are not an inclusive list, but are some of the more prominent spaces, places, art, and figures that shaped the community. Keeping these legacies alive and further preserving others, retains a connection to the past while strengthening a sense of community and pride in South Dallas.

South Dallas Neighborhoods

Dixon Circle

Rose Garden

Bertrand

Wheatly Place

Queen City

Bonton

Ideal, Elite

Romine

Mill City

Dolphin Heights

Charles Rice

Lincoln Manor

South Blvd. Park Row

Colonial Hill

Forest Heights & St. Phillips

Jeffries-Meyers

Architecture and Buildings

Masonic Temple (need specific address)

Hayden Grocery Store

Bama Pie Building

James Madison High School Italian Renaissance style of architecture built in 1916.

Museums & Cultural Heritage

Kathlyn Joy Christian Gilliam Museum

African American Museum

MLK Civil Rights Museum

Arthello Beck Gallery

Juanita Craft

Historical Figures Memoralized by Street Name Dedication

SM Wright -Dallas native, born February 7, 1927 a Pastor, political strategist, and Dallas religious leader. In 1995 then Governor George W. Bush made Wright the first African American to have a Dallas freeway named in his honor.

J.B. Jackson Jr. -civil rights leader, political strategist, founding member of the Dallas Area Rapid Transit Board and real estate broker. He worked with Elsie Faye Heggins to get access ramps placed within South Dallas community from Interstate 45.

Family & Friendly Spaces and Places

MLK Center Library/Recreation

Mildred Dunn Splash Park

Exline Aquatic Center

Juanita Craft Tennis Court

South Dallas Bicycle Club - Al Lipscomb Way

MLK Senior Center

Larry Johnson Recreation Center

Mildred Dunn Recreation Center, Turner Courts

Leo Chaney Park

Rochester Park William Blair Park

Juanita Craft Recreation Center

Willie Mae Butler Park, Dixon Circle

Cultural Artists/ Musicians

Bobbie Humphrey -Flutist Lincoln High School

David Fathead Newman - Ray Charles

Butler Smith - John Coltrane

Red Garland

Shirly McFatter

Belle Roberts Children Choir

South Dallas Concert Choir

William Sidney Pittman

South Dallas Historical Markers

New Hope Baptist Church July 27, 1873 Salem Institutional Baptist Church 1888 African American Museum

All Ican American Museu

Graham Barbershop



Many of the commercial corridors and commercial nodes in South Dallas have struggled for a number of years. Disinvestment both on the private and public side have contributed to the struggles. Targeted strategies for investment in local businesses and entrepreneurs is needed. These strategies need to incorporate and promote equitable economic development policy in South Dallas.

In addition to equitable investment, the corridors and nodes themselves should be reimagined as mixed use corridors and nodes to include both non-residential and residential uses.

C ECONOMIC DEVELOPMENT

GUIDING PRINCIPLES

- Pursue impactful investment opportunities for commercial and residential development and redevelopment
- Promote small businesses and neighborhood-focused businesses to establish SD/FP as a destination.
- Encourage businesses that are compatible with surrounding residences.
- Foster creation of walkable commericial corridors with small businesses, green spaces, pocket parks and recreation.

OVERVIEW

The task force members, reflecting the desires of the community, felt that in order to create economic development in South Dallas, the City should direct funding into small and local businesses while also creating opportunities for new development along major corridors. There are opportunities to make more impactful use of existing funding sources like the South Dallas/Fair Park Opportunity Fund or the Grand Park South TIF. In addition, allowing more mixed use along the corridors would help create economic development opportunities.

ACTION STEPS

Grand Park South TIF

- Revamp TIF Board. Recommend members who have a vested interest in the TIF and South Dallas.
- Provide onboarding and trainings for TIF members in TIF, economic development, and City policies.
- Better utilize TIF funds to support new project including costly infrastructure needs.

Revamp South Dallas/Fair Park Opprunity Fund Board.

- Recruit members citywide with afflications, interests and compassion for SDFP.
- Create and implement a better marketing strategy for the funding source within the community.
- Reallocate a portion of the SDFP Opportunity Fund for a micro

lending program with bridge financing.

Promote growth and expansion of existing Businesses.

• Idenitfy and promote small businesses and neighborhood focused businesses to establish SDFP as a destination.

Economic Development Services

- Promote and market the services of of the economic development office to the community.
- Utilize the Small Business Assistance program to provide funding to local existing businesses and start ups.

Potential Areas for Redevelopment

When considering opportunities for possible future development the task force and community members identified several specific locations that have the potential to act as catalytic projects,

- Review development possibilities and address potential development hurdles at the following:
 - o 2800 and 2900 block of MLK Jr.
 - Medill Street between Al Lipscomb Way.
 - Meadow Street between Al Lipscomb and MLK JR.
 - o 3100 block of South Blvd.
 - Vacant properties on Al Lipscomb Way between Robert B Cullum and Meyers Street.



Much of South Dallas lacks adequate infrastructure including but not limited to; sidewalks, water lines, sewer lines, stormwater, roads and access to the internet. In some cases this is because that infrastructure was not maintained, in other cases it was because that infrastructure was never developed. Moving forward, and looking south to bridge the infrastructure gap in South Dallas, investment in all forms of infrastructure is a priority.

D INFRASTRUCTURE

GUIDING PRINCIPLES

- Weave neighborhoods together by connected streets, sidewalks, access to goods & services and community gathering spaces.
- Increase lighting, safety and police visibility to improve area's image and aesthetic appeal.
- Improve street design & connectivity within the planning area. Address the digital divide by expanding broadband access throughout the area.

OVERVIEW

There is a need for investment in infrastructure throughout South Dallas. There is hardly a street in South Dallas that does not need some type of investment in sidewalks, roadways, water lines, sewer, stormwater, broadband, street lighting and more.

The task force prioritized some of the investment needs where they believed would be the most beneficial for the existing community and future development. Some of those recommendations are shown on the right. A larger list of recommendations is included in the implementation table at the end of the document. Ultimately the five focus areas discussed later in this document is where major infrastructure investments should be prioritized.

ACTION STEPS

Equitable Infrastructure Investment

- Align infrastructure investment with current and future housing needs, emphasizing the interconnectedness of these elements for sustainable and resilient development.
- Review future investment recommendations made by the South Dallas/Fair Park Area plan through an equitable lens to help determine which areas should be prioritized in South Dallas.
- In order to address inequity, the recommendations in this plan should be used to prioritize South Dallas when considering future citywide infrastructure investment.



Well being is about being whole, as individuals and communities; our access to well being is vitial for health, hope, and resilience. The human drive for wellbeing is universal, access to well being is not. This is due to inequities based on race, gender, sexuality, ability, and other factors. These inequities are often reflected in and reinforced by how the benefits and burdens of public investments are distributed, with harms concentrated and accelerated in historically underserved communities.

E COMMUNITY WELL BEING

GUIDING PRINCIPLES

- Implement land use policies, tools, and incentives that support improved health, safety, and quality of life for residents.
- Promote parks, trails and connections to those parks and trails.
- E3 Incentivize access to healthy food stores.

OVERVIEW

The health and well being of the resident of South Dallas factored into a number of action steps in the implementation section of this plan. Investments in infrastructure, additional economic development and job opportunities, improvements in the housing stock and investment in new affordable and compatible housing are all rooted, in part, in acknowledgment that those recommendations all can improve the health and well being of the residents of South Dallas. In addition, the task force wanted to uplift several recommendations from community members that would improve the wellbeing of those in South Dallas. They are listed to the right.

ACTION STEPS

Implement incentives that support improved safety and quality of life for residents

- Select target areas for concentrated crime remediation strategies to reduce violent crime
- Utilize racial equity investment. Designate a Right Care Team specific for South Dallas/Fair Park and reduce the numer of individuals with untreated mental health conditions living on the streets.

Establish a committee for responsible for overseeing the implementation of the SDFP area plan

- Select representatives from the Neighborhood Coalition Group or the existing SDFP Area plan Taskforce to uphold the objectives of the area plan and maintain accountability.
- Partner with DART to continue increasing ridership of DART Go_Link.

South Dallas is home to roughly 8,595 housing units including detached residential, duplexes, townhouses, and apartments. Of those units, approximately 2,118 or 25% are vacant detached residential/ single family and undeveloped properties.

The majority of the existing detached homes were built between 1900 and 1950, and although they were uilt in different styles, they share a number of common design elements including number of stories, rooft type, driveway and garage prominence, and entryway design. Between 1950 and 2010, a relatively small number of homes were built. however since 2010. home building in South Dallas has been on the rise once again.

As recently as 2022, more than 700 residentially zoned lots in South Dallas neighborhoods did not have a structure on them. Members of the task force and the community have been eager to have those properties develop with housing, however, there is growing concern about new homes in South Dallas not having a design that was compatible with the original housing stock. In some cases, as one Task Force member, former Councilwoman Dianne Ragsdale put it, the new homes were, "grossly incompatible" with existing homes.



F HOUSING & DESIGN

GUIDING PRINCIPLES

- Ease displacement pressure on existing reisdents while creating diverse housing options for new residents.
- Align opportunities for new housing development with the needs of diverse residents, considering incomes, age, and diverse family needs.
- Preserve existing housing stock for current homeowners F3 and renters and improve code compliance for unsafe or unmaintained buildings.

South Dallas/Fair Park Area Plan - DRAFT - April 2025

OVERVIEW

There is a strong sense of community throughout South The task force also recognized that in addition to the efforts to be successful, support, investment, and coordination from both the public and private sectors is needed.

Preserving existing housing stock for current homeowners and renters is a priority for this area. Much of the housing stock is relatively affordable compared to other parts of the City, however, that is rapidly changing. The median estimated home value increased from \$165,395 in 2022 to \$220,910 in 2025. With a tight housing market, hundreds of vacant lots, and less expensive land as compared to other parts of the city, South Dallas is on the cusp of significant change, and there is concern about displacement and dilution of its historic and cultural legacy. A number of tools have been discussed to address these concerns including both financial assistance to help with maintenance and retention as well as design overlays to help with preserving neighborhood identity.

South/Dallas Fair Park Area Plan-DRAFT April 2025

Dallas neighborhoods, and there is a long history of preserve existing housing, there is a need for more and different community, resident, and business organizations advocating types of housing in South Dallas, especially with an eye toward for quality and affordable housing in the area. Despite strengthening existing neighborhoods and prioritizing quality disinvestment over the years by both the public and private design. With the concern over "grossly incompatible" home sector, community advocates, residents and non-profits designs, the task force discussed extending design guidance have worked tirelessly to manage, rehabilitate, and develop to not just single-family homes, but to other housing types as housing in South Dallas. However, recent new development well, particularly duplexes, given their popularity right now pressure and rising property values have strained the in the area. Historically in South Dallas, duplexes, according resources and reach of these groups. In the spirit of to one task force member were "just houses with two front continuing this work, the task force recommended a number doors," but similar to new single-family homes, some new of actions to help existing residents maintain their housing, duplexes in South Dallas have been developed largely out promote compatible new housing, and retain the identity of of scale and context with existing housing. The plan calls for established neighborhoods. For these recommendations to duplexes to have the same standards as single-family homes.

> For other housing types, in general, it was recommended that new townhomes, apartments and mixed-use developments be located along major streets including Martin Luther King Blvd, Malcom X Blvd, Elsie Faye Heggins St, 2nd Ave, S. Fitzhugh Ave, Robert B Cullum Blvd, and JB Jackson Blvd; at intersections; and at transit nodes like DART stations. The additional housing would help to bring in jobs, economic development, and amenities to the community.



As recently as 2022, more than 700 residentially zoned lots in South Dallas neighborhoods did not have a structure on them. Members of the task force and the community have been eager to have those properties develop with housing, however, there is growing concern about new homes in South Dallas not having a design that was compatible with the original housing stock. In some cases, as one Task Force member, former Councilwoman Dianne Ragsdale put it, the new homes were, "grossly incompatible" with existing homes.

Different tools and options have been discussed and explored to ensure that new housing in South Dallas is reflective of the design and pattern of established neighborhoods Conservation including Districts, Historic Districts, and Neighborhood Stabilization Given complexities of these processes, immediate market pressures, and a significant number of vacant land available in infill areas, the Task Force and other community representatives agreed that laying the foundation in this plan for amendments to the residential design standards in PD595 would be the most efficient way to address the majority of the resident concerns.



KEY DESIGN ELEMENTS

- 1. Porches in the front
- 2. Garage placement
- 3. Pitched Roof

Building Scale and Form

- 1. Maximum Height
- 2. Reduced pavement/ driveway width in the front

HOUSING & DESIGN ACTION STEPS

Align opportunities for new housing with the diverse needs of residents including income levels, age and stages of life.

- Coordinate with the Housing Department to provide planning, design, and zoning support, where needed, within the Southern Dallas Equity Strategy Area as outlined in the City's Housing Plan.
- Advance the revitalization and redevelopment of the Jefferies-Meyers neighborhood, including providing clarity on the environmental barriers that exist on certain properties.
- Provide strategic and dedicated funding from the Home Improvement and Preservation Program (HIPP) for South Dallas/Fair Park.

Enhance preservation efforts in South Dallas.

- Provide support for the historic designation process in the Queen City neighborhood.
- Coordinate with historic preservation staff to assess other neighborhoods in South Dallas
 to determine interest and eligibility for pursuing historic designation, a conservation
 district, or another similar program with focus on preserving areas of architectural and
 cultural significance.

Preserve existing naturally occurring affordable housing.

- Provide workshops on homestead execptions and the appeal process for property rates.
- Work with Legal Aid of Northwest Texas to host heirship propery education workshops.
- Support external efforts for propery tax reductions.
- Increase home maintenance grant assistance programs for low income homewoners to help stablize aging properties and keep people in their homes.
- Ensure that South Dallas is included in any target areas for the deployment of antidisplacement tools as they are developed and implemented within the city.
- Develop policy requiring developers purchasing City of Dallas real estate to host community meetings to engage surrounding property owners early on in any redevelopment process.

Update PD 595 to incorporate residential design standards for single family zoning districts:

Front Porches

Porches add usable outdoor space to a home, provide shelter from the elements, and create a welcoming feel along the street. Porches should be included with new construction and should define a combination of minimum widths, depth, elevation difference from grade, railing or enclosures, massing of the posts or other elements.

Garage Placement

Garages should not be the prominent feature of the home or the front yard. If there is alley access, garages should be accessed from the alley when possible. Without alley access, garages should be placed in the rear yard if detached and if attached, set back from the front facade of the building. In addition the percentage of the linear feet of garage frontage of the front facade should be limited.

Height

To maintain a more consistent scale between new construction and existing homes, the maximum height of single family homes should be reduced from the current height allowed and measured at the highest roof point not the mid-point of the roof as is the current standard. The height should further be limited to a maximum of 2 and 2.5 stories.

Pitched Roof

Roof type can significantly impact the massing of a home and how it relates to neighboring buildings. New construction should include a roof with some degree of pitch in a more traditional gable or hip style where the pitch would come together.

Minimize Driveway in Front Yards

Impervious cover in the front yard not only impacts design, but stormwater management as well. The paved area in the front yard, including driveways and walkways should be limited to more closely reflect the traditional neighborhood context.

Windows

Windows on the front façade can contribute to an inviting walk up appeal of a home and provide additional eyes on the street promoting an increase in a sense of community. New homes in South Dallas should be a minimum percentage of transparency(windows) on the front façade.

CHAPTER OVERVIEW


Focus areas in the South Dallas/Fair Park Area Plan serve as key areas where efforts and resources should be concentrated to address specific challenges, unlock potential, and stimulate development. These areas were chosen based on their ability to drive meaningful change, such as boosting economic activity, improving community infrastructure, and enhancing quality of life. Focus areas foster collaboration among stakeholders and guide targeted actions to ensure sustainable and impactful outcomes. The focus areas were vetted & prioritized by the taskforce and presented to the broader community. There are other areas of need within in the plan area, however these five areas were selected based on thier opportunity now and their potential to have a positive impact not only to the areas themselves but to the surrounding areas as well.

FCOS SINGUES S


CONTENTS

- A. 2ND AVENUE
- **B. ELSIE FAYE HEGGINS STREET**
- C. MALCOLM X BLVD CORRIDOR
- D. MARTIN LUTHER KING JR. DART STATION
- E. QUEEN CITY NEIGHBORHOOD

FOCUS AREA MAP



This page is intentionally left blank.



Second Ave was once the heart of South Dallas. It was a vibrant street full of store, shops, restaurants and the people of South Dallas. But years of neglect, under investment, limiting development regulations and the absorption of parts of 2nd Ave. into Fair Park has left 2nd Ave a shell of its former self. Current land uses along the street are a scattered mix of office, retail, restaurant and institutional, with a number of vacant properties. Through thoughtful investment and planning Second Ave can once again become a vibrant focal point of South

Dallas.

FUTURE VISION

The future vision for 2nd Ave is that it become a walkable street with retail. restaurants, office, residential and mixed use buildings with an overall focus on entertainment. New buildings should mimic many of the existing

buildings that have a Pre-World War Il style, where the buildings are close to the street with parking either on-street or behind the building. The existing right-of-way of 2nd Ave. (currently four lane undivided) should be examined to determine if a better street design would match a walkable mixed use street. This vision for 2nd Ave aligns with the citywide Neighborhood Mixed Use Placetype which describes low-rise walkable mixed use areas.

RECOMMENDATIONS

To achieve the vision of the walkable mixed use street, the following are recommended:

a change to the zoning along 2nd Ave and between 2nd Ave. and Robert B Cullum should be considered to spur interest and activate ongoing events and activities along the corridor.


a mixed Use Subdistrict within Planned Development 595 should be

considered to allow for retail, personal service uses, office, restaurant, residential, in particular if part of a mixed use building. The subdistrict should also include development standards that encourage the buildings to be located close to the street, be limited to low rise in height,

and remove parking minimums.

The 2nd Ave. merchant association should work with the Dallas Black Chamber of Commerce to host quarterly workshops. Consider updating the zoning for areas identified as Neighborhood Mixed Use to allow for a walkable mix of uses.

FOCUS AREA MAP - FUTURE PLACETYPES





South Dallas/Fair Park Area Plan - DRAFT - April 2025

ELSIE FAYE HEGGINS ST.

CONTEXT

Elsie Faye Heggins is the main thoroughfare in South Dallas along the eastern side of the community. Originally called Hatcher Street, the street was renamed a decade ago in honor of the South Dallas civil rights leader and City council member, Elsie Faye Heggins.

The street is a mixture of residential with commercial nodes at key intersections. Like many of the commercial areas in South Dallas, underinvestment from both the public and private side, has contributed to vacancy and property conditions at the commercial nodes.

FUTURE VISION


During engagement through the area plan process and Forward Dallas 2.0, community members and

task force members spoke about a revitalized street with mixed use nodes at major intersections and increased residential options along the corridor. In particular investment in the commercial area at the intersection of 2nd and Elsie Faye Heggins was highlighted as a potential area for vibrant mixed use development with shopping, dining, and additional residential.

The placetype identified along the corridor is a mix of Neighborhood Mixed Use and Community Residential. Both placetypes are intended for low rise development. The Neighborhood Mixed Use placetype areas are geared towards retail, commercial small office, and residential uses. The Community Residential placetype is primarily focused on smaller scaled residential uses.

RECOMMENDATIONS

Currently, the zoning for the commercial nodes along Elsie Faye Heggins only allows for commercial, retail, office or personal service uses. Residential uses are not allowed. To achieve the future vision, this plan recommends changing the zoning along the commercial areas of Elsie Faye Heggins to allow for both residential and non residential. Allowing residential along this corridor could minimize housing pressure toward the surrounding neighorhoods as well as provide a broader market to the currently struggling commercial areas.



MALCOLM X BLVD CORRIDOR

For Review Use Only - Draft

CONTEXT

Dallas is one of the only cities in the country where Malcolm X Blvd. and Martin Luther King Jr. Blvd. intersect. The focus on this area is a natural extension of it's vibrant history and culture. The corridor is lined with numerous businesses, schools, churches, and community organizations, playing a key role in the communities' daily life, economic development, and revitalization efforts. This street also passes through the historic Queen City neighborhood. South Malcolm is divided into three segments.

Segment one is the intersection of Dr. MLK JR Blvd. and S. Malcolm X to the intersection of S. Malcolm X to Warren Ave. In this segment there are vacant retail storefronts with sidewalks ripe for small business development all the way to Birmingham Ave. There are bus shelters along the way with sidewalks. Commercial properties end at Warren Ave.

Segment two is the intersection of S. Malcolm X to Warren Ave to Pine Street. At the intersection of Twyman street the properties transition back to residential. Metropolitan Ave. @ Malcolm X abuts to Wheatley Place,

another historic African American community within South Dallas. There are numerous vacant lots along the way that are ideal for new residential housing that will be compatible with the existing housing.

Romine Ave @Malcolm X Ave is the residential neighborhood of Queen City with additional pockets of retail space opportunities, across the street is the historic Oakland cemetery. This segment would be most appropriate for single family housing opportunities or small multifamily. Existing small multifamily at Eugene Street. Opportunity Park is across the street.

Segment three is the Intersection of S. Malcolm X and Pine Street to Elsie Faye Heggins Street. Currently there are small local existing businesses being a mix of personal services. Numerous places of worship along the corridor throughout all segments.


FUTURE VISION

During engagement of ForwardDallas 2.0, residents selected Neighborhood Mixed Use place type along South Malcolm X Blvd. This placetype incorporates a mix of commercial, retail, office, and residential building types. Low rise buildings, ideally two stories is appropriate along this corridor.

RECOMMENDATIONS

A recommended zoning change to Mixed Use Subdistrict within Planned Development 595 to allow for retail, personal service uses, office, restaurant, residential, in particular if part of a mixed use building. That subdistrict should also include development standards that encourage the buildings to be located close to the street, be limited to low rise in height, and have no parking minimums.

The plan recommends changing segment one and three to a mixed use subdistricts to allow for retail, personal service uses, office, restaurant, residential in particular in mixed use buildings. That subdistrict should also include development standards that encourage the building to close to the street, be limited to low rise in height and integrated into the design of the community. The second segment remain residential zoning district with any new non-single family housing on the corridor appropriately incorporated into the existing residential neighborhoods in both form and massing.



MARTIN LUTHER KING JR. DART STATION

For Review Use Only - Draft

CONTEXT

In 2013, the City in partnership with the community produced the MLK Dart Station Area plan. That plan suggested that the area around the DART station be developed as a mixed use area with retail. restaurants, employment centers and housing. The plan details the many reasons why the area is a good location for redevelopment. Including it's access to the rail line. proximity to Fair Park, and large parcel sizes. The plan suggests the scale of that development include mainly low rise buildings with potential mid-rise at certain locations.

Since that plan was created there has been a considerable amount of development of mid-and-high rise residential and mixed use buildings in Deep Ellum and even some proposed across I-30 on Exposition closer to South Dallas. In addition many property owners around the MLK Station and along Robert B Cullum and JB Jackson have worked to put together an updated vision for the area through the Pointe South Revitalization Group.


FUTURE VISION

Much like the 2013 plan, the future vision for the area is a mixed use area with retail, restaurants, office. employment and housing. The updated vision includes allowing more housing and allowing more midto-high-rise development in certain areas. The high rise development should occur closer to the MLK station and along Robert B Cullum and JB Jackson. Mid-rise or lowrise development would taper away from the station and from Robert B Cullum and JB Jackson. The new buildings should have active uses on the ground floors and be integrated into the public realm. Public ROW and public land, both from DART and City of Dallas should be examined to understand how it can be best used to achieve the future vision of the area.

This vision for the station area closely matches both the citywide Regional and Community Mixed Use Placetypes which describe both high rise and mid -rise mixed use areas respectively.

RECOMMENDATIONS

To achieve the vision of the walkable mixed use area with mid-and high -rise development, the zoning should be reviewed around the MLK Station and along Robert B Cullum and JB Jackson. A Mixed Use Subdistrict within Planned Development 595 should be considered that allows for retail, personal service uses, office, restaurant, residential. Development standards that encourage the buildings to be located close to the street, provide active uses on the ground floor, allow mid to high rise depending on the placetype, and have no parking minimums should be considered. In addition to changes in the zoning, the City of Dallas should prioritize investments in infrastructure around the DART MLK station according the guidance in this plan collaboration with existing property owners according to the specific locations found in the Infrastructure implementation table.



QUEFN CITY QUEFN CITY QUEFN COD NEIGHBORHOOD NEIGHBORHOOD

QUEEN CITY

CONTEXT

Queen City neighborhood is a nationally recognized African American community whose buildings date from 1915 to 1945. Portions of the neighborhood were placed on the national register in 1995. Architecturally it is recognized for its late 19th and early 20th century American Movements: Bungalow/ Craftsman style homes.

The neighborhood is two miles southeast of downtown, and once served as the physical nucleus of South Dallas' African American suburban development. It is located only a few blocks south of what was known as the "color line", which until World War II delineated African American residential development from white neighborhoods to the north and west.

The nationally recognized historic boundaries of Queen City include the approximately eight blocks south of Martin Luther King Jr. Boulevard (MLK). The district includes the equivalent of four blocks along Atlanta Street, extending from Cooper Street on the northwest, to Eugene Street on the southeast and the 3700 block of Dildock street parallel to and immediately east of Atlanta Street.

Queen City became a focal point for African American business owners. artists, musicians, and professionals. During this area planning process Ms. Eva Jones, Queen City Neighborhood Association President and task force member begin working with her community along with the Office of Historic Preservation to request that Queen City be recognized locally as a historic district to preserve and protect the historical structures within Queen City. As of June 3, 2024, the Landmark Commission authorized a hearing to consider initiation of the historic designation process to establish a historic overlay district.

FUTURE VISION


With local landmark designation, Queen City will be recognized both locally and nationally as an essential asset to the history and culture of African American life in Dallas, Texas. New construction homes within the historic district will blend seamlessly with the existing homes.


The future Placetype for the area is Community Residential which, encompasses the largest percentage of land within Queen City and is primarily made up of single-family homes. Parks such as

Exline Recreational facility, schools, and places of worship like Salem International Baptist Church are interspersed throughout providing focal points for community activity. Spaces like the Hayden Grocery Store should be identified for a historical marker y the community. Through historic preservation efforts Queen City can stablilize and preserve the remaining historic character and charm of the tudors, bugalows, and other architectural styles from Warren Ave. to Eugene Street.

RECOMMENDATIONS

Queen City to continue the process of a historical overlay district through the Historic Preservation Office. The community will identify the new boundaries of the historic district and select the most favorable architectural styles to preserve. The remaining homes outside of the historical overlay district will follow any future updates to the residential design standards in PD595, including. consistent roof styles, building heights, access and placement of garages, and front porches. It is also recommended that Queen City Neighborhood Association starts the process of identifing historical places and spaces for historical markers.





LAND USE + ZONING

Theme Goal: Amend land use zoning and regulations, repurpose vacant and underutilized land use that contribute positively to the surrounding areas.

Land Use and Zoning Recommendations for Planned Development 595

Objective	Action Step	Lead	Key Partners
Protect the historic and cultural fabric of neighborhoods in South Dallas by preventing "grossly incompaitible" new residential development.	Initiate the community process to review and consider amendments to PD595 to create design standards for single family detached and duplex housing.	PDD	CPC & City Council
	Continue to support the Queen City neighborhood in the Historic District Designation process.	PDD	Queen City Neighborhood Association
Prioritize the redevelopment of commercial corridors and nodes into mixed	Review the zoning in PD595 for areas designated as a Regional Mixed Use Placetype to allow for a mix of uses in Mid-to High-Rise buildings.	PDD	CPC & City Council
use areas.	Review the zoning in PD595 for areas designated as a Community Mixed Use Placetype to alow for a mix of uses in Low-to Mid-Rise buildings.	PDD	CPC & City Council
	Review the zoning in PD595 for areas designated as a Neighborhood Mixed Use Placetype to allow for a mix of uses in Low-Rise buildings.	PDD	CPC & City Council
Redevelop specific areas with a mix of uses that contribute to the	Review development possibilities and address potential development hurdles on the 2800 and 2900 block of MLK Jr.	PDD	Housing Eco Dev
surrounding areas	Review development possibilities and address potential development hurdles on Medill Street between Al Limpscomb Way and Relevant.	PDD	Housing and Eco Dev
	Review development possibilities and address potential development hurdles on Meadow Street between Al Limpcomb and MLK Jr.	PDD	Housing and Eco Dev
	Review development possibilities and address potential development hurdles on along the 3100 block of South Blvd.	PDD	Housing and Eco Dev
	Review development possibilities and address potential development hurdles on vacant properties on Al Limpscomb Way between Robert B Cullum and Meyers Street. along the 3100 block of South Blvd.	PDD	Housing and Eco Dev
Prioritize infill development and redevelopment on properties without an active land use.	Continue to work with Housing department to strategically target reinvestment areas.	PDD	Housing
Missing Middle Housing & creating additional housing and ownership options for South Dallas residents	Amend the PD to allow for properties in the Duplex zoning district to be subdivided so that each household can own both their half of the structure and land.	PDD	CPC & City Council
	If private zoning changes are applied for from single detached to single single attached, those changes should consider that same design standards for single family detached.	PDD	CPC, City Council and the South Dallas Neighborhood Coalition
	Amend the PD to allow ADUs with development standards from the ADU overlay district.	PDD	CPC & City Council

For Review Use Only - Draft

LAND USE + ZONING

Theme Goal: Amend land use zoning and regulations, repurpose vacant and underutilized land use that contribute positively to the surrounding areas.

Land Use and Zoning Implementation Table			
Objective	Action Step	Lead	Key Partners
Review and update the allowable uses in PD595 to be consistent with today's resident, business and market needs.	Amend the PD to allow Catering Services land use by right in mixed use subdistrict	PDD	Housing & ECO DEV
	Amend the PD to allow Restaurant with all food to go land use by right in mixed use subdistrict	PDD	CPC & City Council
	Amend the PD to allow Massage land use as an accessory land use to other Personal Service land uses	PDD	CPC & City Council
	Amend the PD to include Vape Shops as a Tobacco Store not allowed by right	PDD	CPC & City Council
	Review parking mandate in the PD and if not addressed through citywide policies reduce or in some cases remove the parking mandate from the PD	PDD	CPC & City Council
Monitor the status of Plan implementation on a yearly basis.	Continue to monitor and review placetype maps with ForwardDallas 2.0 to ensure community feedback is expressed in the final future placetype map.	PDD	CPC & City Council

South Dallas/Fair Park Area Plan - DRAFT - April 2025 South/Dallas Fair Park Area Plan - DRAFT April 2025 South/Dallas Fair Park Area Plan - DRAFT April 2025

^{*}Low, Mid, and High Rise buildings are as defined in ForwardDallas 2.0 adopted Comprehensive plan.

HOUSING + DESIGN

Theme Goal: Preserve existing housing stock for current homeowners and renters, ease displacement pressure on existing residents, and align opportunities for creating diverse housing options for new residents.

Housing + Neighborhood Implementation Table			
Objective	Action Step	Lead	Key Partners
Align opportunities for new housing development with the needs of diverse residents, considering incomes,	Keep South Dallas/Fair Park area to be an equity strategy target area for the City of Dallas Housing Plan.	Housing	PDD
	Completion of revitalized Jefferies-Myers neighborhood including providing clarity on environmental issues.	Housing	PDD
age and diverse family needs.	Target funding from Home Improvment & Preservation (HIPP), Targeted Rehab Program, & Minor Home Rehabilitation Program for South Dallas Fair Park.		
	Designate home repair dollars for Queen City specifically to preserve existing homes and maintain affordability.	Housing	PDD & Queen City Neighborhood Association
Anti-Displacement Efforts	Implement preservation initiative to support redevelopment of South Dallas.	PDD	HRNA
	Work with Legal Aid of Northwest Texas to host heirship property education workshops annually	Legal Aid of Northwest Texas	PDV, Housing, South Dallas Neighborhood Coalition
	Support external efforts for property tax reductions.	PDD	Housing External Agencies
	Prioritize neighborhood stabilization efforts in neighborhoods identified as most susceptible to displacement.	PDD	
	Provide educational workshops on homestead exemptions and the appeal process for property rates.	Legal Aid of Northwest Texas	PDD, Housing
	Explore opportunities through the City's Community Land Trust program to promote and preserve affordable homeownership.	Housing	PDV
	Implement additional anti-displacement policies created by Builder of Home for the Housing Department.	Housing	PDV
	Support external efforts for property tax reductions		
	Develop policy requiring developers purchasing City of Dallas real estate to host engagement meeting and submit authentic sign in sheet.	PDV	Council & CPC
	Incorporate future comprehensive urban design guidelines within the city's Notice of Funding Availability (NOFA) procurement, selection, and review process for multifamily projects.	Housing	PDV

For Review Use Only - Draft

INFRASTRUCTURE

Theme Goal: Weave neighborhoods together by connected streets, sidewalks, access to goods, and services and community gathering spaces. Strategically deploy and monitor City investment: Bond Program, CDBG, Parks, Transportation and Public Works.

	Infrastructure Implementation Ta	ble	
Objective	Action Step	Lead	Key Partners
Equitable Infrastructure investment	Review future investments citywide in Dallas thorough an Equitable lense to help determine which areas should be priotized citywide.	PDV	Public Works
	Review future investments South Dallas made after the recommendations of this plan through an equitable lens to help determine which areas should be priotized in South Dallas.	PDV	District 7 Bond Committee
Prioritized Recommended Infrastructure improvements to address current needs	Monitor Racial Equity Plan as it relates to infrastructure gaps where intentional historical disinvestment previously occurred. Address areas that are severly lacking in sidewalk, road, broadband, water and park infrastructure. Fast track bonds projects in disinvested areas.	PDV	Office of Equity
	Elsie Faye Heggins-Second -Completely rebuild the signalized intersection to upgrade the physical infrastructure. Elsie Faye Heggins-Scyene- Completely rebuild the signalized intersection to upgrade the physical infrastructure.	TRN	Public Works, District 7 Bond Committee & City Council
	Malcolm X-Elm to Warren- Design and consruct context sensitive street design improvements wider sidewalks, pedestrian lighting, street trees, crosswalks in different paving associated with Fair Park. Include 150 block and 2500 block.	TRN	Public Works, District 7 Bond Committee & City Council
	Al Lipscomb-Malcolm X- Completely rebuild the signalized intersection to upgrade the physical infrastructure.	TRN	Public Works, District 7 Bond Committee & City Council
	Malcolm X-MLK Jr Blvd-Completely rebuild the signalized intersection to upgrade the physical infrastructure.	TRN	Public Works, District 7 Bond Committee & City Council
	1200 S Trunk Ave Street resurfacing local streets (Al Lipscomb Way to Park Row Ave.)	TRN	Public Works, District 7 Bond Committee & City Council
	2500-2600 Myers Street-Street Resurfacing local streets (Ash Lane to Al Lipscomb Way)	TRN	Public Works, District 7 Bond Committee & City Council
Create an Equitable and Connected Network of Complete Communities with Access to Diverse Housing, Service and Employment opportunities.	Prioritize connecting traditionally disconnected and underserved populations to employment, education, parks, food, and health services by periodically reviewing mix of land uses in these communities and how they are accessed.	PDV	

ECONOMIC DEVELOPMENT

Theme Goal: Pursue catalytic opportunities for commerical and residential development and promote small businesses and neighborhood-focused businesses to establish SD/FP as a destination.

Economic Development Implementation Table			
Objective	Action Step	Lead	Key Partners
Grand Park South TIF (Tax Increment Financing)	Revamp TIF board. Revamp TIF Board. Recruit members who have a vested interest in the TIF and South Dallas.	PUD	Council & CPC
	Provide onboarding and trainings for TIF members, economic development, and city policies.	ECO DEV	Council
	Better utlilize TIF funds to support new project including costly infrastructure needs.	ECO DEV	TIF ADMIN
Revamp SDFP Opportunity Fund Board	Recruit members citywide with affiliations, interests and compassion for SDFP.	OED	Entrepreneur Center
	Create and implement a better marketing strategy for the funding source within the community.	OED	State Fair of Texas; Point South Revitialization Committee, DISD
	Reallocate a portion of SDFP Opportunity Funds for a micro lending and bridge financing.	OED	
Promote growth and expansion of existing businesses	Identify and promote small businesses and neighborhood- focused businesses to establish SD/FP as a destination.	PUD	Small Business Center & ECO DEV
	Work with Black Chamber of Commerce to host quarterly workshops with the 2nd Avenue Merchants Association.	Small Business Center	Entrepreneur Center Manager
Small Business Center	Promote and market the services of the small business center to the community. Utilize Small Business Center to provide funding to local existing businesses and start ups.	OED	OED

South Dallas/Fair Park Area Plan -DRAFT - April 2025

COMMUNITY WELL BEING

Theme Goal: Implement land use policies, tools, and incentivies that support improved health, safety, and quality of life for residents.

Community Wellbeing Implementation Table			
Objective	Action Step	Lead	Key Partners
Implement incentives that support improved safety, and quality of life for residents.	Select target areas for concentrated crime remediation strategies to reduce violent crime.	Office of Integrated Public Safety Solution	DPD Code Community Prosecution
	Utilize racial equity investment, designate a Right Care Team Specific for South Dallas/Fair Park. Reduce untreated mental health on the streets.	OIPSS	DPD, Behavioral Health
Establish committee responsible for overseeing the implementation of the SDFP Area Plan	Select representatives from the Neighborhood Coalition Group or existing SDFP Area plan Taskforce to uphold the objectives of the area plan and hold the city staff accountable.	PUD	Neighborhood Coalition Group
	Partner with DART to continue increase ridership of DART Go-Link	DART	NCCOG

HISTORY + CULTURE

Theme Goal: Protect, support, and celebrate South Dallas/ Fair Park history, culture, people, and architecture.

History & Culture Implementation Table			
Objective	Action Step	Lead	Key Partners
Empower Residents to uplift and preserve	Assist Queen City Neighborhood with Historic District Process.	SD/FP Community	Historic Preservation
historic character of the communit and places of significant value	Protect SD/FP history and culture by Neighborhood Coalition and SDFP Taskforce selecting a history and culture committee to pursue historical markers for Ms. Pearl C Anderson home and Hayden Grocery Store.		
	Celebrate history by archiving historical information and creating a living document via online publication. Assist existing Neighborhood Association and the	SD/FP Community	Historic Preservation
	creation of new ones in South Dallas.		
	Work with existing cultural organizations such as South Dallas Cultural to collect oral histories from South Dallas Residents.	SD/FP Community	South Dallas Cultural Center Dallas Public Libraries
	Collect historical artifacts photos, videos, memorabilia) of prominent South Dallas families to tell the story of various South Dallas communities.		
Recommended cultural corridors to support local small businesses and entrepreneurs.	Work with local sororities and faternities chapters that serve South Dallas and identify historical and cultural events of significance.		
	Document and collect history and cultural experiences from Fair Park in reference to African Americans. (State Fair Classic Prarie View A&M & Grambling State)	SD/FP Community	Economic Dev.

South/Dallas Fair Park Area Plan-DRAFT April 2025

SDFP AREA PLAN

CITY OF DALLAS PLANNING + DEVELOPMENT MARCH 2025