


Plotted by: ##### Plot Date: 4/9/2018 10:56 AM

- Drawing: S:\Projects\CAD043\DWG\CAD043-LS.dwg Saved By: Station5 Save Time: 4/9/2018 10:55 AM



SYMBOL	COMMON/BOTANICAL NAME	SIZE	SPACING	QUANTITY	REMARKS
BC	BALD CYPRESS / TAXODIUM DISTICHUM	3" CALIPER	AS SHOWN	3	6' MINIMUM SPREAD; MINIMUM 12' HEIGHT; FULL ROUNDED HEAD 6' MINIMUM BRANCHING HEIGHT; NURSERY GROWN.
LO	LIVE OAK / QUERCUS VIRGINIANA	3" CALIPER	AS SHOWN	8	6' MINIMUM SPREAD; MINIMUM 12' HEIGHT; FULL ROUNDED HEAD 6' MINIMUM BRANCHING HEIGHT; NURSERY GROWN.
LE	LACEBARK ELM / ULMUS PARVIFOLIA	3" CALIPER	AS SHOWN	22	6' MINIMUM SPREAD; MINIMUM 12' HEIGHT; FULL ROUNDED HEAD 6' MINIMUM BRANCHING HEIGHT; NURSERY GROWN.
OG	OCTOBER GLORY RED MAPLE / ACER RUBRUM 'OCTOBER GLORY'	3" CALIPER	AS SHOWN	2	6' MINIMUM SPREAD; MINIMUM 12' HEIGHT; FULL ROUNDED HEAD 6' MINIMUM BRANCHING HEIGHT; NURSERY GROWN.
BO	BUR OAK / QUERCUS MACROCARPA	3" CALIPER	AS SHOWN	3	6' MINIMUM SPREAD; MINIMUM 12' HEIGHT; FULL ROUNDED HEAD 6' MINIMUM BRANCHING HEIGHT; NURSERY GROWN.
ERC	EASTERN RED CEDAR / JUNIFERUS VIRGINIANA	3" CALIPER	AS SHOWN	22	6' MINIMUM SPREAD; MINIMUM 12' HEIGHT; FULL ROUNDED HEAD 6' MINIMUM BRANCHING HEIGHT; NURSERY GROWN.
RB	FOREST PANSY REDBUD / CERCIS CANADENSIS 'FOREST PANSY'	2" CALIPER	AS SHOWN	4	5' MINIMUM SPREAD; MINIMUM 8' HEIGHT; 2" MIN. CAL.; FULL HEAD NURSERY GROWN
LGM	LITTLE GEM MAGNOLIA / MAGNOLIA GRANDIFLORA 'LITTLE GEM'	2" CALIPER	AS SHOWN	11	5' MINIMUM SPREAD; MINIMUM 8' HEIGHT; 2" MIN. CAL.; FULL HEAD NURSERY GROWN
NRS	FOSTER'S HOLLY / ILEX x ATTENUATA 'FOSTERI'	15 GALLON	AS SHOWN	6	FULL PLANTS
	SAVANNAH HOLLY / ILEX x ATTENUATA 'SAVANNAH'	10 GALLON	AS SHOWN	73	FULL PLANTS
	UPRIGHT ROSEMARY / ROSMARINUS OFFICINALIS	7 GALLON	AS SHOWN	75	FULL PLANTS
	TEXAS SAGE / LEUCOPHYLLUM FRUTESCENS	5 GALLON	AS SHOWN	73	FULL PLANTS
	INDIAN HAWTHORN 'SNOW' / RAPHIOLEPIS INDICA 'SNOW WHITE'	3 GALLON	AS SHOWN	114	FULL PLANTS
	RED YUCCA / HESPERALOE PARVIFLORA	3 GALLON	AS SHOWN	34	FULL PLANTS
	COLOR GUARD YUCCA / YUCCA FILAMENTOSA 'COLOR GUARD'	3 GALLON	AS SHOWN	54	FULL PLANTS
	ENGLISH LAVENDER / LAVANDULA ANGUSTIFOLIA	3 GALLON	AS SHOWN	147	FULL PLANTS
	DWARF FOUNTAIN GRASS / PENNISETUM ALOPECUROIDES 'HAEMELN'	3 GALLON	18" O.C.	634	FULL PLANTS
	BLUE PACIFIC JUNIPER / JUNIPERUS CONFERTA 'BLUE PACIFIC'	3 GALLON	36 O.C.	8	FULL PLANTS
	LITTLE BLUESTEM GRASS / SCHIZACHYRIUM SCOPARIUM	1 GALLON	24" O.C.	63	FULL PLANTS
	ANNUAL COLOR TO BE SELECTED BY OWNER	4" POTS	8" O.C.	1,025	FULL PLANTS
	COMMON BERMUDA GRASS	SOLID SOD	SQUARE	75,700	MINIMUM 100% COVERAGE




A. MINIMUM TEN (10) FOOT LANDSCAPE EDGE PROVIDED
B. 6' HT. MASONRY SCREENING WALL OR ORNAMENTAL METAL FENCING PROVIDED.
C. 1-3" CAL. CANOPY TREE / 50 LF OF LANDSCAPE EDGE
1/210 LF OF FRONTRAGE / 50 LF = 24 - 3" CAL. TREES REQUIRED.
PROVIDED: 24 - 3" CALIPER AND GREATER CANOPY TREES PROVIDED

1. STABILIZE SOIL BELOW ROOT BALL PRIOR TO PLANTING TO PREVENT TREE FROM SETTLING.
2. TOP OF ROOTBALL SHALL 1" TO 2" ABOVE FINISHED GRADE.
3. ALL WIRE ROPE AND SYNTHETIC MATERIALS SHALL BE REMOVED COMPLETELY FROM ROOTBALL AND REMOVE TOP 1/3 OF BURLAP
4. PLANTING PITS SHALL BE SQUARE, SIDES OF PITS SHALL BE THOROUGHLY SCARIFIED/ROUGHENED TO ELIMINATE FLARED AS SHOWN IN TYPICAL DETAIL

- B. TREE
- B. LOOSEN NATIVE BACKFILL (NO SOIL AMENDMENTS IN CONTRACT)
- C. WATER RETENTION BASIN
- D. 3" DEPTH MULCH AS SPECIFIED
- E. FINISH GRADE
- F. 2 1/2 DRYNALL SCREW (UNFINISHED)
- G. 2" X 2" X 4" CROSS MEMBER (UNTREATED LUMBER). **NOTE:** CROSS MEMBERS TO BE ORIENTED PARALLEL TO NORTH / SOUTH BEARING AND SHALL BE PROPORTIONAL IN LENGTH TO ROOT BALL (4' MIN).
- H. 2" X 2" X 4" STAKE WITH 18" MIN. TAPE (UNTREATED LUMBER)
- I. REMOVE TOP 1/3 OF BURLAP SURROUNDING ROOTBALL AFTER INSTALLATION (TO PREVENT "WICKING" OF MOISTURE) X. DIMENSION EQUAL TO "Y" Y. DIMENSION EQUAL TO "X"
- J. ROOTBALL TO SET ON UNDISTURBED NATIVE SOIL.

Studio 13 Design Group, PLLC.
386 W. Main Street
Lewisville, Texas 75057
469-635-1900

TBAE Firm #BR643



City of Dallas, Dallas County, Texas

LS2 of 2

CITY OF DALLAS CASE #D178-007